



- 6 FRESH WATER SUPPLY / ALIMENTARE CU APA BRUTA
- 7 WATER STORAGE / REZERVOARE DE APA
- 8 POTABLE WATER / APA POTABILA
- 9 DOMESTIC WASTEWATER / APE UZATE MENAJERE

STREAM / CIRCUITUL	1	2	3	4	5	6	7	13	14
FLOW / DEBITUL (m <sup>3</sup> / h)									
YEAR-3	239.20	8.00	231.20	226.20	5.00	210.40	15.80	5.00	5.00
YEAR-10	239.20	8.00	231.20	226.20	5.00	210.40	15.80	5.00	5.00
YEAR-15	251.34	8.00	243.30	238.30	5.00	210.40	27.94	5.00	5.00
Long Average / Media pe perioada de viata a proiectului	238.20	7.9	230.30	225.30	5.00	207.40	17.97	5.00	5.00

ALL FLOWS ARE FOR AVERAGE PRECIPITATION AND EVAPORATION. / TOATE DEBITELE SUNT CONSIDERATE LA VALORI MEDII ALE PRECIPITATIILOR SI EVAPORARII.

LOM = LIFE OF MINE / DURATA DE VIA TA A PROIECTULUI

				Owner / Beneficiar: S.C. ROSIA MONTANA GOLD CORPORATION S.A.		Exhibit / Plansa 4.1.14	
Elaborated by / Ing. Nicolai Mircea Cristian		Note / Note: Information provided by RMGC / datele au fost puse la dispozitie de beneficiar		Documentati / Documentatie: ENVIRONMENTAL IMPACT ASSESSMENT REPORT / RAPORT DE EVALUARE A IMPACTULUI ASUPRA MEDIULUI		Title / Denumire Plan: FRESH WATER & DOMESTIC WASTEWATER FLOWCHART / SISTEMELE DE ALIMENTARE CU APA SI CANALIZARE	
Verified by / Ing. Gabriel Neamtu		Scale / Scara: 		Chapter / Capitol 4 : POTENTIAL IMPACT/ IMPACT POTENTIAL		Date / Data: March / Martie 2006	
Manager project / Ing. Sorin Berchinis		Date / Data: 		Section / Sectiunea 4.1 : WATER / APA			